



DELHI URBAN SHELTER IMPROVEMENT BOARD
Government of National Capital Territory of Delhi
OFFICE OF THE EXECUTIVE ENGINEER (C-6)
1, Kilokri, Ring Road, New Delhi – 110 014

No.:NIQ No.06/WJ-6996/TC/EE/C-6/DUSIB/2017-18

Dated : 01.08.2017

NOTICE INVITING QUOTATION NO.06

Sealed percentage rate quotations are invited from the registered/specialized agency of appropriate class for under mentioned work by the undersigned on behalf of DUSIB **upto 3.30 PM** on dated **03.08.2017** which will be opened on the same day at **4.00 PM** in the presence of intending quotationers or their representatives in the **office of the Executive Engineer, C-6** at **1, Kilokri, Ring Road, Opp. Maharani Bagh, New Delhi – 110 014**. The schedule of **item/quotation** documents including terms and conditions can be had from the office of the undersigned **up to 3.00 PM** on dated **03.08.2017**.

Name of Work : **Pay & Use JSC**
Sub Head : **Renovation of 23 seater JSC at JJ Basti Nehru Navjeevan Camp, Kalkaji by providing WC and tile flooring.**
Estimated Cost : **Rs.92,414.00**
Time : **15 days.**

TERMS & CONDITIONS :

1. The work shall be carried out as per CPWD specifications.
2. Cement/Steel required shall be arranged by the Agency and same shall confirm to relevant specifications/I.S. Code.
3. Payment shall be made as per actual measurement at site of work.
4. No T&P shall be issued.
5. No extra charges shall be paid except for the rates quoted.
6. Conditional quotations shall be liable to rejection.
7. For any disputes the mater shall be referred to SE-II, DUSIB for final decision and the same shall be binding upon both the parties.
8. Time allowed for completion of work shall be **15 days** which shall be reckoned from the date after the date of approval from competent authority.
9. Income Tax @ 2%, Security Deposit @ 10%, Sale Tax/VAT @ 4% and Labour Cess @ 1% shall be deducted from bills of Contractor. Security shall be refunded after six months of completion of work
10. Necessary statutory deductions will be made as per prevailing law.
11. Work shall be completed to the satisfaction of Engineer-in-Charge.
12. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.
13. The Contractors are required to comply with labour rules w.r.t. leave medical and minimum wages etc.

Distribution :

1. Notice Board
2. Office copy
3. Guard file.

Executive Engineer / C-6

Executive Engineer / C-6

DELHI URBAN SHELTER IMPROVEMENT BOARD
GOVT. OF NCT OF DELHI
OFFICE OF THE EXECUTIVE ENGINEER C-06

Name of Work: Pay and Use (JSC)

Sub Head: Renovation of 23 seater JSC at JJ Basti Nehru Nav Jeevan Camp, Kalkaji by providing W.C. and tile Flooring.

Sl. No.	Description of work	No. or Qty.	Unit	Estimate	AMOUNT	
				Figure	Rs.	P
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	2.78	cum	5466.30	15196.31	
2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	50.00	kg	90.10	4505.00	
3	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer -in-Charge, in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	8.76	sqm	836.65	7329.05	
4	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS :15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4Coarse sand) including pointing the joints with white cement and matching pigment etc. complete.	27.83	sqm	785.40	21857.68	
5	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	200.00	sqm	7.60	1520.00	
6	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats) .	200.00	sqm	32.00	6400.00	
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	90.09	sqm	48.50	4369.37	
8	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	1.39	sqm	3267.56	4541.91	
9	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	27.83	sqm	28.20	784.81	
10	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all loads including all lifts involved.	30.00	cum	123.70	3711.00	
11	Providing and fixing white vitreous china water closet squatting pan (Indian type) Orissa pattern W.C. pan of size 580x440 mm	23.00	each	1405.30	32321.90	
12	Providing and fixing PTMT bib cock of approved quality and colour . 15mm nominal bore, 86 mm long. Weighing not less than 88 gms.	11.00	each	156.05	1716.55	
13	Providing and fixing PTMT, push cock of approved quality and colour . 15 mm nominal bore, 98 mm long. Weighing not less than 75 gms.	5.00	each	152.55	762.75	
					105016.33	
Less 12% on cost index as per order of Govt. of NCT of Delhi					-12601.96	
Total					92414.37	

EEC-06

AE-I C 06