



DELHI URBAN SHELTER IMPROVEMENT BOARD

Government of National Capital Territory of Delhi
OFFICE OF THE EXECUTIVE ENGINEER (C-6)

1, Kilokri, Ring Road, New Delhi – 110 014

No.: **NIQ No.18/WJ-6996/TC/EE/C-6/DUSIB/2017-18**

Dated : 13.11.2017

NOTICE INVITING QUOTATION NO.18

Sealed percentage rate quotations are invited from the registered/specialized agency of appropriate class for under mentioned work by the undersigned on behalf of DUSIB by **3.30 PM** upto **15.11.2017** which shall be opened on the same day at **4.00 PM** in the presence of intending quotationers or their representatives in the **office of the Executive Engineer, C-6 at 1, Kilokri, Ring Road, Opp. Maharani Bagh, New Delhi – 110 014**. The schedule of **item/quotation** documents including terms and conditions can be had from the office of the undersigned up to **3.00 PM** on dated **15.11.2017**.

NOW : **Swachh Bharat Mission (SBM)**
Sub Head : **Construction of septic tank in JSC at JJ Basti Indira Kalyan Vihar near Dustbin, Okhla Industrial Area, Ph.-I**
Estt. Cost. : **Rs.8,00,203.00**
Time : **30 days.**


TERMS & CONDITIONS :

1. The work shall be carried out as per CPWD specifications.
2. Cement/Steel required shall be arranged by the Agency and same shall confirm to relevant specifications/I.S. Code.
3. Payment shall be made as per actual measurement at site of work.
4. No T&P shall be issued.
5. No extra charges shall be paid except for the rates quoted.
6. Conditional quotations shall be liable to rejection.
7. For any disputes the mater shall be referred to SE-II, DUSIB for final decision and the same shall be binding upon both the parties.
8. Time allowed for completion of work shall be **30 days** which shall be reckoned from the date after the date of approval from competent authority.
9. Statutory taxes and Security Deposit shall be deducted from bills of Contractor. Security shall be refunded after three months of completion of work.
10. Necessary statutory deductions will be made as per prevailing law.
11. Work shall be completed to the satisfaction of Engineer-in-Charge.
12. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.
13. The Contractors are required to comply with labour rules w.r.t. leave medical and minimum wages etc.

Distribution :

1. Notice Board
2. Office copy
3. Guard file.

//
Executive Engineer / C-6


Executive Engineer / C-6 13/11/17

Sl. No.	Ref. Code	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
					Figure	Words	
1.00	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (excluding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m; disposed earth to be levelled and neatly dressed All kinds of soil	206.37	cum	155.60	Rupees One Hundred & Fifty Five - Paise Sixty Only	32111.17
2.00	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering lead up to 50m and lift upto 1.5m	165.1	cum	112.40	Rupees One Hundred & Twelve - Paise Fourty Only	18557.24
3.00	2.26	Extra for every additional lift of 1.5 m or part thereof in:					
3.10	2.26.1	All kinds of soil .	65	cum	46.25	Rupees Fourty Six - Paise Twenty Five Only	3006.25
4.00	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering . All work upto plinth level.					
4.10	4.1.3	1:2:4(1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	3.3	cum	5466.30	Rupees Five Thousand Four Hundred & Sixty Six - Paise Thirty Only	18038.79
4.20	4.1.10	1:5:10(1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	9.75	cum	4004.00	Rupees Four Thousand & Four Only	39039.00
5.00	Appd Item	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:1.5:3 (1 Cement :1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.34	cum	7282.50	Rupees Seven Thousand Two Hundred & Eighty Two - Paise Fifty Only	2476.05
6.00	5.9	Centring and shuttering including strutting, propping etc. and removal of form for :					
6.10	5.9.3	Suspended floor, roofs, landings, balconies and access platform.	39.14	sqm	401.65	Rupees Four Hundred & One - Paise Sixty Five Only	15720.58
6.20	5.9.5	Lintels, beams, plinth beams, griders, bressumers and cantilevers.	3.09	sqm	332.15	Rupees Three Hundred & Thirty Two - Paise Fifteen Only	1026.34
7.00	5.22	Steel Reinforcement for R.C.C work including straightening, cutting, bending placing in position and binding all complete. Upto plinth level					
7.10	5.22.6	Thermo-Mechanically Treated bars. (TMT bars)	3148.75	kilogram	68.10	Rupees Sixty Eight - Paise Ten Only	214429.88

		<p>grade concrete for reinforced cement concrete work, using cement content as per approved design mix, manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work, including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering, shuttering finishing and reinforcement, including cost of admixtures in recommended proportions as per IS : 9103 to accelerate / retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge.</p> <p>(Note :- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/recoverable separately).</p>					
8.10	5.33.1	All works upto plinth level	24.85	cum	6644.60	Rupees Six Thousand Six Hundred & Forty Four - Paise Sixty Only	165118.31
9.00	6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in					
9.10	6.1.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	71.59	cum	4918.65	Rupees Four Thousand Nine Hundred & Eighteen - Paise Sixty Five Only	352126.15
10.00	13.4	12 mm cement plaster of mix:					
10.10	13.4.1	1:4 (1 cement : 4 coarse sand)	103.64	sqm	172.30	Rupees One Hundred & Seventy Two - Paise Thirty Only	17857.17
11.00	13.5	15 mm cement plaster on rough side of single or half brick wall of mix:					
11.10	13.5.1	1:4 (1 cement : 4 coarse sand)	1.2	sqm	200.05	Rupees Two Hundred - Paise Five Only	240.06
12.00	13.16	6 mm cement plaster to ceiling of mix:					
12.10	13.16.1	1:3 (1 cement : 3 fine sand)	33	sqm	134.70	Rupees One Hundred & Thirty Four - Paise Seventy Only	4445.10
13.00	13.18	Neat cement punning	181.84	sqm	41.40	Rupees Forty One - Paise Fourty Only	7528.18
14.00	17.35	Providing and fixing soil, waste and vent pipes					
14.10	17.35.1	100 mm dia.					
14.20	17.35.1	Sand cast iron S & S pipe as per IS : 1729	8	metre	859.00	Rupees Eight Hundred & Fifty Nine Only	6872.00
15.00	17.39	Providing and fixing plain bend of required degree					
15.10	17.39.1	100 mm					

Ref. Code	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT	
				Figure	Words	Rs.	P
15.20	17.39.1 .1	Sand cast iron S&S as per IS : 1729	4	each	434.50	Rupees Four Hundred & Thirty Four - Paise Fifty Only	1738.00
16.00	17.56	Providing and fixing terminal guard:					
16.10	17.56.1	100 mm					
16.20	17.56.1 .1	Sand cast iron S&S as per IS : 1729	4	each	248.65	Rupees Two Hundred & Forty Eight - Paise Sixty Five Only	994.60
17.00	17.58	Providing lead caulked joints to sand cast iron / centrifugally cast (spun) iron pipes and fitting of diameter					
17.10	17.58.1	100mm	8	each	243.75	Rupees Two Hundred &	1950.00
18.00	19.19	Providing and fixing in position precast R.C.C. manhole cover and frame of required shape and approved quality					
18.10	19.19.3	H D -20					
18.20	19.19.3 .1	Circular shape 560 mm internal diameter.	4	each	1511.55	Rupees One Thousand Five Hundred & Eleven - Paise Fifty Five Only	6046.20
		Less 12% on cost index as per order of Govt. of NCT of Delhi	909321.07	each	0.12	Rupees - Paise Twelve Only	-109118.53
		Total					800202.54