



DELHI URBAN SHELTER IMPROVEMENT BOARD

Government of National Capital Territory of Delhi
OFFICE OF THE EXECUTIVE ENGINEER (C-6)

1, Kilokri, Ring Road, New Delhi – 110 014

NIQ No.53/WJ-6996/TC/EE C-6/ae-i/DUSIB/2017-18

Dated : 27.02.2018

NOTICE INVITING QUOTATION NO.53

Sealed percentage rate quotations are invited from the registered/specialized agency of appropriate class for under mentioned work by the undersigned on behalf of DUSIB upto 3.30 PM on dated 28.02.2018 which will be opened on the same day at 4.00 PM in the presence of intending quotationers or their representatives in the office of the Executive Engineer, C-6 at 1, Kilokri, Ring Road, Opp. Maharani Bagh, New Delhi – 110 014. The schedule of item/quotation documents including terms and conditions can be had from the office of the undersigned up to 03.00 PM on dated 28.02.2018.

Name of Work : MLA LAD FUND
Sub Head : Soil Investigation for construction of Community Facility/
Community Hall building at JJ Colony, Tigri.
Estimated Cost : Rs.45,434/-
Time : 15 days.

TERMS & CONDITIONS :

1. The work shall be carried out as per CPWD specifications.
2. Cement/Steel required shall be arranged by the Agency and same shall confirm to relevant specifications/I.S. Code.
3. Payment shall be made as per actual measurement at site of work.
4. No T&P shall be issued.
5. No extra charges shall be paid except for the rates quoted.
6. Conditional quotations shall be liable to rejection.
7. For any disputes the mater shall be referred to SE-II, DUSIB for final decision and the same shall be binding upon both the parties.
8. Time allowed for completion of work shall be 15 days which shall be reckoned from the date after the date of approval from competent authority.
9. Income Tax @ 2%, Security Deposit @ 10% and Labour Cess @ 1% shall be deducted from bills of Contractor. Security shall be refunded after six months of completion of work
10. Necessary statutory deductions will be made as per prevailing law.
11. Work shall be completed to the satisfaction of Engineer-in-Charge.
12. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.
13. The Contractors are required to comply with labour rules w.r.t. leave medical and minimum wages etc.

Distribution :

1. Notice Board
2. Office copy
3. Guard file.


Executive Engineer / C-6

Name of work : MLA LAD FUND
 Sub-Head: Soil Investigation for Construction of Community Facility/ Community Hall building at JJ Colony, Tigri.

ABSTRACT OF COST

S.N	Ref.	Description of work	No. or Qty	Unit	Estimated Rate		Amount Rs. P
					Figure	Words	
1		Making 150mm dia bore for soil investigation in all types of using soil shell and auger method up to depth of 20 metres or up to refusal which ever occurs earlier, performing standard penetration test as per IS2131:1981 including transportation, assembling of plant and machinery for drilling holes at various locations. Collection of samples at every 1.50m depth/interval or as required including transportation of collected soil samples to the laboratory and conducting all necessary lab tests and compilation of test results in order to analysis of the safe bearing capacity of soil and details of foundation etc. and as required for soil investigation attached with submission of four copies of detailed soil investigation report containing all details, graphs, test results, conclusions and recommendations etc. and to interact with the department up to the final depth of foundation is decided and for any modification / clarification in the report as and when required all complete as per direction of Engineer in Charge. (G.L to 20.00 metres below)	45.00	Metre	1147.33	Rs. One thousand one hundred forty seven & Paise thirty three only	51629.85

Less 12% on cost index as per order of Govt. of NCT of Delhi

51629.85
 -6195.58
 45434.27