



DELHI URBAN SHELTER IMPROVEMENT BOARD

Government of National Capital Territory of Delhi
OFFICE OF THE EXECUTIVE ENGINEER (C-6)

1, Kilokri, Ring Road, New Delhi – 110 014

NIQ No.54/WJ-6996/TC/EE C-6/AE-V/DUSIB/2017-18

Dated : 12.03.2018

NOTICE INVITING QUOTATION NO.54

Sealed percentage rate quotations are invited from the registered/specialized agency of appropriate class for under mentioned work by the undersigned on behalf of DUSIB upto **3.30 PM** on dated **13.03.2018** which will be opened on the same day at **4.00 PM** in the presence of intending quotationers or their representatives in the **office of the Executive Engineer, C-6 at 1, Kilokri, Ring Road, Opp. Maharani Bagh, New Delhi – 110 014**. The schedule of **item/quotation** documents including terms and conditions can be had from the office of the undersigned up to **03.00 PM** on dated **13.03.2018**.


Name of Work : **EIUS**
Sub Head : **P/L sewer line and regarding of nallah for disposal of pond water in Karpuri Thakur Camp, Kalkaji**
Estimated Cost : **Rs.5,17,779/-**
Time : **30 days.**

TERMS & CONDITIONS :

1. The work shall be carried out as per CPWD specifications.
2. Cement/Steel required shall be arranged by the Agency and same shall confirm to relevant specifications/I.S. Code.
3. Payment shall be made as per actual measurement at site of work.
4. No T&P shall be issued.
5. No extra charges shall be paid except for the rates quoted.
6. Conditional quotations shall be liable to rejection.
7. For any disputes the matter shall be referred to SE-II, DUSIB for final decision and the same shall be binding upon both the parties.
8. Time allowed for completion of work shall be **30 days** which shall be reckoned from the date after the date of approval from competent authority.
9. Statutory taxes such as Income Tax @ 2%, Security Deposit @ 10% and Labour Cess @ 1% shall be deducted from bills of Contractor. Security shall be refunded after six months of completion of work
10. Necessary statutory deductions will be made as per prevailing law.
11. Work shall be completed to the satisfaction of Engineer-in-Charge.
12. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.
13. The Contractors are required to comply with labour rules w.r.t. leave medical and minimum wages etc.

Distribution :

1. Notice Board
2. Office copy
3. Guard file.


Executive Engineer / C-6

DELHI URBAN SHELTER IMPROVEMENT BOARD

GOVT. OF NCT OF DELHI

OFFICE OF THE EXECUTIVE ENGINEER C-06

Name of Work: EIUS							
Sub Head : P/L sewer line and regrading of nállah for disposal of pond water in karpuri thakur camp, Kalkaji.							
Sl. No.	Ref. Code	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
					Figure	Words	
1	1.1.1	Carriage of materials by mechanical transport including loading unloading and stacking of lime moorum building rubbish upto 5.00 km					
2	1.1.1	Extra for beyond 5 km upto 10 km	77.50	cum	122.46	Rupees One Hundred & Twenty Two - Paise Fourty Six Only	9490.65
3	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	77.50	cum	9.24	Rupees Nine - Paise Twenty Four Only	716.10
4	2.10.1.2	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, inlayers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : All kinds of soil Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	13.62	cum	157.50	Rupees One Hundred & Fifty Seven - Paise Fifty Only	2145.15
5	2.12	Extra for excavating trenches for pipes, cables, etc in all kind of soil for depth exceeding 3 m in depth but not exceeding 4.5 m (Rate is over corrsponding basic item for depth upto 1.5 metre)	90.00	metre	280.30	Rupees Two Hundred & Eighty - Paise Thirty Only	25227.00
6	2.28.1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift upto 1.5 m. All kinds of soil.	90.00	metre	726.97	Rupees Seven Hundred & Twenty Six - Paise Ninety Seven Only	65427.30
7	4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	155.00	per 100 sqm	1245.75	Rupees One Thousand Two Hundred & Fourty Five - Paise Seventy Five Only	1930.91
8	4.2.3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., up to floor five level, excluding the cost of centering, shuttering and finishing : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	1.20	cum	4004.00	Rupees Four Thousand & Four Only	4804.80
			1.62	cum	6450.00	Rupees Six Thousand Four Hundred & Fifty Only	10449.00

Sl. No.	Ref. Code	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT	
					Figure	Words	Rs.	P
9	4.20.1.1	Providing and laying in position ready mixed plain cement concrete, with cement content as per approved design mix and manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for plain cement concrete work, including pumping of R.M.C. from transit mixer to site of laying and curing, excluding the cost of centering, shuttering and finishing, including cost of curing, admixtures in recommended proportions as per IS : 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge. Note : 1) Excess/less cement used than specified in this item is payable/recoverable separately. All works up to plinth level: M-15 grade plain cement concrete (cement content considered @ 240 kg/cum).	15.50	cum	5996.70	Rupees Five Thousand Nine Hundred & Ninety Six - Paise Seventy Only		92948.85
10	5.9.3	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform.	70.00	sqm	401.65	Rupees Four Hundred & One Paise Sixty Five Only		28115.50
11	5.9.6	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts.	21.60	sqm	453.35	Rupees Four Hundred & Fifty Three - Paise Thirty Five Only		9792.36
12	5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars.	1380.00	kg	68.10	Rupees Sixty Eight - Paise Ten Only		93978.00
13	6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	12.27	cum	4677.25	Rupees Four Thousand Six Hundred & Seventy Seven - Paise Twenty Five Only		57389.86
14	13.4.1	12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	21.60	sqm	172.30	Rupees One Hundred & Seventy Two - Paise Thirty Only		3721.68
15	13.5.1	15 mm cement plaster on rough side of single or half brick wall of mix :1:4 (1 cement: 4 coarse sand)	21.60	sqm	200.05	Rupees Two Hundred - Paise Five Only		4321.08
16	13.18	Neat cement punning	43.20	sqm	41.40	Rupees Fourty One - Paise Fourty Only		1788.48
17	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	17.25	cum	1302.30	Rupees One Thousand Three Hundred & Two Paise Thirty Only		22464.68

Sl. No.	Ref. Code	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT	
					Figure	Words	Rs.	P
18	16.53	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m) having 50 no rounds per 6 metre length, upto 3m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) /Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	60.00	metre	287.05	Rupees Two Hundred & Eighty Seven - Paise Five Only	17223.00	
19	19.6.3	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 250 mm dia. R.C.C. pipe	90.00	metre	468.60	Rupees Four Hundred & Sixty Eight - Paise Sixty Only	42174.00	
20	2.21 Hort. DSR	Excavation in dumped stones or malba including stacking of serviceable and unserviceable material separately and disposal of unserviceable lead up to 50 metre and lift upto 1.50 metre disposed material to be neatly dressed	77.50	Cum	267.50	Rupees Two Hundred & Sixty Seven - Paise Fifty Only	20731.25	
21	Appd item	Desilting of Nallah / Drain in running flow and under foul condition for depth not exceeding 1.5 metre including removal of stones, bricks, brick bats, garbage, silt, mud, polythene and sewage if any etc. and diversion of flow of sludge if required and removing the same away from cluster at the place as directed by Engineer-in-charge. Disposed silt to be leveled and neatly dressed.	159.60	cum	49.22	Rupees Fourty Nine - Paise Twenty Two Only	7855.51	
22	Appd item	Providing and fixing precast reinforced cement concrete slab on existing drains excluding the cost of centring shuttering finishing and reinforcement with mix 1:2:4 (1 cement : Coarsesand : 4 graded stone aggregate 20mm nominal size)	11.50	cum	5712.20	Rupees Five Thousand Seven Hundred & Twelve - Paise Twenty Only	65690.30	
Total								65690.30
Less 12% on cost index as per order of Govt. of NCT of Delhi								588385.46
Total								70606.26
								517779.20

EE C-6

AE-I C-06