

DELHI URBAN SHELTER IMPROVEMENT BOARD
GOVERNMENT OF NCT OF DELHI
OFFICE OF THE EXECUTIVE ENGINEER/C-2

3rd floor, Circle Office Bldg.
,Road No.28, Shivaji Place,
Raja Garden, New Delhi-110027

No. NIQ No. ~~32~~/EE-C2/DUSIB/2017-18/D-844

Dated: 07.04.2018

NOTICE INVITING QUOTATIONS

Executive Engineer/C-2 on behalf of DUSIB invites quotations on percentage rate basis in sealed cover from intending agencies who are registered with DDA,CPWD,BSNL,I&FC,MCD,MES etc and having sufficient experience in anti termite treatment / pest control.

S.N.	Name of work	Estimated Cost (Rs)	Time Allowed for completion of work
1	NOW:- Construction of 7620 EWS LOW COST HOUSING at Savda Ghewra Phase-II Sub-Head :- Making arrangement for anti-termite treatment for composite centre/ community hall at site no.III Savda Ghewra Ph-III	Rs.32,279.00	90 Days.

The quotations should reach to the Office of the Executive Engineer,C-2,DUSIB, 3rd floor, Circle Office Bldg., Road No.28, Shivaji Place, Raja Garden, New Delhi-110027 latest by 3.00 PM on 10.04.2018 which shall be opened on the same day at 3:30PM in the presence of intending quotationers or their representatives. The intending quotationers may collect the schedule of quantity and other information from the office of the undersigned by 3:00 PM on 10.04.2018. The terms and conditions of the NIQ are as follows:-

Terms and Conditions Attached.

Detail of item attached



EXECUTIVE ENGINEER-C-2
DUSIB

N10-01 (2018-19)

PRELIMINARY ESTIMATE

NOV:- C/o Composite Centre/ Community Hall at Site No.III at Savda Ghewra Ph.-III.

SH:- Making arrangement for anti- termite treatment.

SN	Ref. No	Description of Item	Qty.	Unit	Rate	Amt.
1	2.34.1	Supplying chemical emulsion in sealed containers including delivery as specified Chlorpyrifous / Lindane emulsifiable concentrate of 20%	30.20	litre	185.95	5,615.69
2 (a)	2.35.1.1	Diluting and injecting chemical emulsion for POST-CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) :chemical emulsion @ 7.5 litres / sqm of the vertical surface of the substructure to a depth of 300 mm including excavation channel along the wall & rodding etc. complete:With Chlorpyrifos/ Lindane E.C. 20% with 1% concentration	81.98	metre	15.40	1,262.49
b)	2.35.2.1	Diluting and injecting chemical emulsion for POSTCONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) Along the external wall below concrete or masonry apron using chemical emulsion @ 2.25 litres per linear metre including drilling and plugging holes etc.With Chlorpyrifous / Lindane E.C.20% with 1% concentration	81.98	sqm	22.70	1,860.95
c)	2.35.3.1	Diluting and injecting chemical emulsion for POST CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) Treatment of soil under existing floors using chemical emulsion @ one litre per hole, 300 mm apart including drilling 12 mm diameter holes and plugging with cement mortar 1:2 (1 cement:2 coarse sand) to match the existing floor:With Chlorpyrifous / Lindane E.C.20% with 1% concentration	235.00	sqm	118.90	27,941.50


Less 12% as per GNCTD

36,680.63
-4,401.68
32,278.95

Say Rs.

32,279.00


7/4/18
EE C-2


AE-VIII/C-2

NID - 01 (2018-19)


Name of work: - c/o Composite Centre / Community Hall at site No. III, Savda-Ghewra Ph-III

SM:- Making Arrangement for anti termite treatment.

scope of work.

- (1) Post/pre construction anti termite treatment along the vertical surface of substructure to a depth of 300mm.
- (2) Along the external walls of the premises below concrete or masonry apron
- (3) Treatment of soils under floors.
- (4) Being a specialised job, "specialized agencies of this nature of work will be considered.
- (5) The agency will have to give guarantee bond for 3 years on non-judicial stamp paper of Rs 50/- after completion of work.
- (6) After six months proper check shall be provided by agency.
- (7) 10% security shall be deducted from the bill of the contractor as a guarantee money.


EEC-2


J. G. Singh
AE-VII