



Delhi Urban Shelter Improvement Board
Govt. of N.C.T. of Delhi
Office of the Executive Engineer, C-04
First Floor, Office cum Shopping Complex,
New Ranjit Nagar New Delhi-110008
Email ID: eec4.dusib@gmail.com

NIQ No.02 /EEC-4/DUSIB/2018-19 /D-180

Dated: 26/06/19


NOTICE INVITING QUOTATION NO.02

Sealed percentage/item rate quotations are invited from the registered/specialized agency of appropriate class for under mentioned work by the undersigned on behalf of DUSIB upto **3:00 PM** on dated **28.06.2019** which will be opening on the same day at **3:30PM** in the presence of intending quotaioners or their representatives in the office of the **Executive Engineer, C-4 at 1st Floor, Office Cum Shopping Complex, New Ranjit Nagar, New Delhi 110008**. The schedule of **item/quotation** documents including terms and conditions may be obtained from the office of Executive Engineer, C-4 on submission of an application along with a Demand Draft amounting to **Rs.3000/-** in favour of EEC-4 DUSIB (security demand draft will be refunded to unsuccessful bidders).

Name of Work : **Construction Of BVK/C.Hall**
Sub Head : **Development of tubewell bore at BVK at Pocket-II Paschim Puri, Madipur. (PMS: 12129)**
Estimated Cost : **Rs.45,736/-**
Time : **15 days**

TERMS & CONDITIONS

1. The work shall be carried out as per CPWD specifications.
2. Cement/steel required shall be arranged by the agency and same shall confirm to relevant specification/I S Code.
3. Payment shall be made as per actual measurement at site of work.
4. No T & P shall be issued.
5. No extra charges shall be paid expect for the rates quoted.
6. Conditional quotations shall be liable to rejection.
7. For any disputes the mater shall be referred ro SE-II, DUSIB for final decision and the same shall be binding upon both the parties.
8. Time allowed for completion of work shall be 15 days which shall be reckoned from the date after the date of approval from competent authority.
9. Statutory taxes shall be deducted from bills of contractor. Security shall be refunded after on month of completion of work.
10. Necessary statutory deductions will be made as per prevailing Law.
11. Work shall be completed to the satisfaction of Engineer-in-charge.
12. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.
13. The contractors are required to comply with labour rules w.r.t leave medical and minimum wages etc.


Executive Engineer, C-4, DUSIB

NOW: C/o BVK BVK Community Hall

SH: Development of tubewell bore at BVK at Pocket-II Paschim Puri, Madipur. (PMS: 12129)

S.no.	DSR Ref.	ITEM	QTY	UNIT	Rate	Amount
1	23.3.2	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge. 150 mm nominal size dia	19.00	mtr	572.3	10873.70
2	23.12	Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for required time till well is fully developed, measuring yield of well by "V" notch method or any other approved method, measuring static level & draw down etc. by step draw down method, collecting water samples & getting tested in approved laboratory, i/c disinfection of tubewell, all complete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge.	20.00	hours	542.2	10844.00
3	23.8	Gravel packing in tubewell construction in accordance with IS: 4097, including providing gravel fine/ medium/ coarse, in required grading & sizes as per actual requirement, all complete as per direction of Engineer- in-charge.	4.00	cum	1175.60	4702.40
4	App.	S/f 3x4 sqm mm PVC insulated and PVC sheathed copper conductor flat submersible cable complete etc. as reqd. ISI mark (MR)	66.00	mtr	189.00	12474.00

5	App.	S/F 6mm dia steel rope for protection of submersible pu,p set as reqd. (MR)	54.00	mtr	42.00	2268.00
6	App.	S/F pf 25mm dia G.I. Pipe 'B' class in soft soil etc as reqd ISI mark (MR)	12.00	mtr	190.00	2280.00
8	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved unicipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial 'lead, for all leads including all lifts involved.	2	cum	120.55	241.1
Total						43683.20
Add 15.69%						6853.89
Total						50537.09
Less 9.5%						4801.02
Total						45736.07
Say						45736.00