## DELHI URBAN SHELTER IMPROVEMENT BOARD GOVERNMENT OF N.C.T. OF DELHI OFFICE OF THE EXECUTIVE ENGINEEER, C-1, Raja Garden, Near DTC Bus Terminal, New Delhi-110027

NIQ No.02/EEC-1/DUSIB/2019-20/D-6子の

Dated: 11.12.2019

## NOTICE INVITING QUOTATION

Executive Engineer, C-1 DUSIB on behalf of Delhi Urban Shelter Improvement Board invites quotations from intending agencies who are registered either with DDA, MCD, CPWD, BSNL(Civil Wing), I&F,MES, Railway etc. in appropriate class, on percentage rate basis in sealed

cover for the following works:-

SL. NO	Name of work	Estimated Cost	Time of Completion
1.	N.O.W: Pay & Use JSC SH: Repair of cracked wall in JSC at JJC Behind Commercial Centre Mayapuri	Rs. 44904.00	15 days

The firms who wish to participate in quotation shall submit their quotation along with the following documents, failing which their quotation is liable to be rejected.

- 1. Copy of their registration certificate.
- 2. Copy of pan card.
- 3. Copy of Registration under GST.

The quotations should reach to the office of the Executive Engineer, C-1, DUSIB, Raja Garden, New Delhi-110027 latest by 3.00 PM on 13.12.2019 which shall be opened on 13.12.2019 at 3.30 PM in the presence of intending quotationers or their representatives.

The intending quotationers may collect the schedule of quantities on DUSIB website and other information from the office of the Executive Engineer, C-1, DUSIB. The terms & Conditions of the quotation are as follows:-

- 1. The work shall be carried out as per CPWD specifications.
- 2. Payment shall be made as per actual measurement at site of work.
- 3. No T&P shall be issued., water is to be arranged by agency.
- 4. Conditional quotations shall be liable to rejection.
- 5. For any disputes the matter shall be referred to SE-I DUSIB for final decision and the same shall be binding upon both the parties.
- 6. Statutory recoveries shall be deducted from the bills of contractor as per rules.
- 7. Work shall be completed to the satisfaction of Engineer-in-charge.
- 8. Debarred/blacklisted agencies shall not be permitted to submit quotations.

1. NOTICE BOARD

2. Publication on DUSIB Website

**EXECUTIVE ENGINEER, C-1** 

## OFFICE OF THE EXECUTIVE ENGINEER C-1 DELHI URBAN SHELTER IMPROVEMENT BOARD GOVT OF NCT OF DELHI

Name of Work: Pay & Use JSC.

a.	Ref. of DSR	pair of cracked wall in JSC at JJC behind back side of commercial centre Mayapuri.  Description	Owentity	Unit	Rate (Rs.)	Amount in
	4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering. All work upto plinth level.1:5:10(1 cement: 5 coarse sand: 10 graded stone aggregate 40 mm nominal size)	Quantity 0.32	cum	4209.05	Rs. 1346.90
	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	1.90	Cum	5481.95	10415.71
	6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth inCement mortar 1:6 (1 cement: 6 coarse sand)	1.84	culm	4751.65	8743.04
		Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar	1.50	Cum	842.75	1264.13
	14.80.2	Providing & fixing White vitreous china water closet squatting pan (Indian type) along with "S" or "P" trap including dismantling of old WC seat and "S" or "P" trap at site complete with all operations including all necessary materials, labour and disposal of dismantled material i/c malba, all complete as per the direction of Engineer-in charge Orissa pattern W.C Pan of size 580x440 mm	3.00	dos.	2127.85	6383.55
5	11.36	Providing and fixing lst quality ceramic glazed wall tiles conforming to IS: 1562; (thickness to be specified by the manufacturer), of approved make, in all colours, shade except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, i skirting, risers of steps and dados, over 12 mm thick bed of cement mortal 1:3 (cement: 3coarse sand) and jointing with grey cement slurry @ 3.3kg per sam, includin pointing in white cement mixed with pigment of matching shade complete	s n 1 15.56	Sqm	744.80	11589.09

