

NIQ No.02/EEC-4/DUSIB/2020-21/D-475

Dated: 16.09.2020

NOTICE INVITING QUOTATION

Executive Engineer(C-4), DUSIB, on behalf of Delhi Urban Shelter Improvement Board invites quotations from intending agencies on percentage basis in sealed cover for the following work:

S.No.	Name of Work	Estimated Cost	Earnest Money	Time of Completion
1.	NOW: Pay & Use JSC SH: C/o platform for MTV at Indira Gandhi Camp, Mayapuri Chowk, (JSC Code: 25MJ0439).	Rs.46445/-	Rs.930/-	30 days

The quotations along with copy of Registration, PAN Card, GST Registration should reach the office of the Executive Engineer, C-4, DUSIB, First Floor, DDA Shopping Complex, Ranjeet Nagar, New Delhi-110008 latest by 03:00 PM on 18.09.2020 which shall be opened on same day i.e. on 18.09.2020 at 03:30 PM in the presence of E.E.(C-4), AE concerned, AAO(C-4). The intending quotaioners may collect the schedule of quantities and other information from the office of the Executive Engineer (C-4), DUSIB. The terms and conditions of the NIQ are as follows:

TERMS & CONDITIONS

1. The work shall be carried out as per CPWD specifications 2019 Vol. – I & II with upto date correction slips as per direction of Engineer-in-Charge.
2. Payment shall be made as per actual measurement at site of work and payment will be made after acceptance of report of Competent Authority/Engineer-in-Charge.
3. No T&P shall be issued by the Department.
4. No extra charges shall be paid except for the rate quoted.
5. Conditional quotations shall be liable to rejection.
6. For any disputes the matter shall be referred to Chief Engineer – I, DUSIB, for final decision and the same shall be binding upon both the parties.
7. Necessary statutory deduction will be made as per prevailing law.
8. Work shall be completed to the satisfaction of Engineer-in-charge.
9. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.
10. The Earnest Money amount to Rs.930/- (Rupees Nine Hundred Thirty Only) @ 2% of the estimated cost of work in the shape of Pay Order/Demand Draft in favor of E.E.C-4, DUSIB put to NIQ along with necessary documents will be submitted.

NOTICE BOARD

[Handwritten Signature]
16/9/2020

Executive Engineer,C-4,DUSIB

NOW: Pay & Use JSC

Sub Head: C/o platform for MTV at Indira Gandhi Camp, Mayapuri Chowk, (JSC Code: 25MJ0439). (PMS: 13084)

SCHEDULE

S. No.	DSR Ref	Particulars	Quantity	Unit	Rate (in Rupees)	Amount
1	2.1.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift up to 1.5 m, as directed by Engineer-in-Charge: All kinds of soil	36.00	Sqm	53.00	1908.00
2	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. :All kinds of soil.	5.25	Cum	166.40	873.60
3	6.1.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	1.40	Cum	4970.30	6958.42
4	4.20.1.1	Providing and laying in position ready mixed plain cement concrete, with cement content as per approved design mix and manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for plain cement concrete work, including pumping of R.M.C. from transit mixer to site of laying and curing, excluding the cost of centering, shuttering and finishing, including cost of curing, admixtures in recommended proportions as per IS : 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge. Note : 1) Excess/ less cement used than specified in this item is payable/ recoverable separately. All works up to plinth level: M-15 grade plain cement concrete (cement content considered @ 240 kg/cum).	4.53	Cum	6190.70	28043.87

5	Apdd	Providing and laying dry brick aggregate 40 mm nominal size in foundation and plinth or under floor at all levels including spreading and ramming in layers as directed by Engineer-in-Charge.	5.35	No.	1229.25	6576.49
						44360.38
		Add @ 15.69% as per DSR 2016				6960.14
		Total				51320.52
		Less @ 9.5% Cost Index				4875.45
		Total				46445.07
		Say				46445.00