

DELHI URBAN SHELTER IMPROVEMENT BOARD
OFFICE OF THE DY. DIRECTOR (HORT.)

1st floor, Community Hall,
C-block, Raghbir Nagar,
New Delhi-110027

N.I.Q. No.06/Dy.Dir.(Hort.)/DUSIB/2020-21/D-146

Dated:- 21/10/2020

NOTICE INVITING QUOTATION

Item rate Quotation is invited in the office of the undersigned at the above mentioned address on behalf of the Delhi Urban Shelter Improvement Board.

S.No.	Name of work & Sub-Head	Esstt. Cost	Time for completion of work
1	N.O.W.:- C/O S.V. (Revenue) SH:-Repair of Boundary Wall of Shishu Vatika at Shahbad Daulatpur.	Rs.43,159.00	15 days


The last date of receipt of quotations-----23.10.2020 (upto 3.00 P.M.)

The date of opening of quotations-----23.10.2020 (3.30 P.M.).

The quotations will be opened by the undersigned in the presence of intending quotationers or their authorized representatives. The Dy. Director (Hort., DUSIB/ Competent Authority reserve the right to accept or reject all quotations or any one quotation.

NOTE:- Documents to be submitted with quotation at the office of Dy. Dir.(Hort.) (Self certified).


1. Copy of Valid Registration papers.
2. Copy of Pan No.
3. Copy of Registration with G.S.T.


Dy. Director (Hort.)
21/10/2020
D.U.S.I.B.

NOTICE BOARD

Name of Work: Construction of Shishu Vatika (Revenue)**Sub-head :- Repair of Boundary wall of Shishu Vaika at Shahbad Daulatpur .**

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate	Rate in words	AMOUNT Rs. P
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	3.26	cum			
2	Washed stone grit plaster on exterior walls of height upto 10 metre above ground level in two layers, under layer 12mm cement plaster 1:4 (1 cement: 4 coarse sand), furrowing the under layer with scratching tool, applying cement slurry on the under layer @ 2 Kg of cement per square metre, top layer 15mm cement plaster 1:1/2:2 (1 cement: 1/2 coarse sand : 2 stone chipping 10mm nominal size), in panels with groove all around as per approved pattern including scrubbing and washing the top layer with brushes and water to expose the stone chippings ,complete as per specification and direction of Engineer-in- charge (Payment for providing grooves shall be made separately).	34.49	sqm			
3	Forming groove of uniform size in the top layer of washed stone grit plaster as per approved pattern using wooden battens, nailed to the under layer including removal of wooden battens, repair to the edges of panels and finishing the groove complete as per specifications and direction of the Engineer-in-charge : 15 mm wide and 15 mm deep groove	85.12	metre			
Total estimated cost in Figures						
Add 15.69 % Above as per Delhi Govt Rule						
Less 9.50 % as per Delhi Govt Rule						


Dy. Dir(Hort)
A.E(H)
J.E(H)