




DELHI URBAN SHELTER IMPROVEMENT BOARD

Government of National Capital Territory of Delhi

OFFICE OF THE EXECUTIVE ENGINEER (C-6)

1, Kilokri, Ring Road, New Delhi – 110 014



NIQ No.: 01 /WJ-6981/EEC6/AE-Iv/DUSIB/2020-21/D- 83 Dated : 23.02.2021

NOTICE INVITING QUOTATION

NOW : Pay & Use (JSC)
SH : **Providing and relaying blocks sewer line for JSC Code No.47CJ0817 at JJ Basti Janta Jeevan Camp opposite Vayusenabad Tigri, Part – I, near Dustbin, A-Block.**
Estt. Cost: 96,554.00
Time Allowed: 15 days

The Executive Engineer (C-06) on behalf of DUSIB invites percentage rate quotations from eligible registered contractors of CPWD, Railways, MES and Civil Wing of BSNL, MCD, DDA, NDMC, Delhi Jal Board, IF&C, Delhi. However, the blacklisted and/or those contractors who have been debarred from future tendering in any Department shall not be eligible.

The contractor who wishes to participate in quotation for above work shall submit their quotation by 24.02.2021 upto 2.00 PM alongwith the following documents at the office of the Executive Engineer (C-06) and the same shall be opened at same place at 3.00 PM:

- 1) Copy of Registration Certificate of the Firm.
- 2) Copy of PAN Card
- 3) Copy of GST Registration.
- 4) Demand Draft in favour of Executive Engineer (C-06) amounting to Rs.5,000/-

TERMS & CONDITIONS :

1. Payment shall be made as per actual measurement at site of work and payment will be made after acceptance of report of Competent Authority/ Engineer-in-Charge..
2. Conditional quotation shall be liable to rejection.
3. Cement/Steel required shall be arranged by the Agency and same shall confirm to relevant specifications/I.S. Code.
4. Time allowed for completion of work shall be **15 DAYS** which shall be reckoned from the date after the date of approval from Competent Authority.
5. No T&P shall be issued by the Department.
6. No extra charges shall be paid except for the rate quoted.
7. For any disputes the matter shall be referred to Chief Engineer – I, DUSIB, for final decision and the same shall be binding upon both the parties.
8. Necessary statutory deduction will be made as per prevailing law.
9. Work shall be completed to the satisfaction of Engineer-in-Charge.
10. Taxes as applicable as on date shall be deducted from the bill of Contractor, Security shall be deducted @ 10% of each bill and same shall be refunded after three months of the completion of work.
11. The Contractor is required to comply with labour rules w.r.t. leave medical and minimum wages etc.

23.2.21
EXECUTIVE ENGINEER (C-06)

- 4/c -

**DELHI URBAN SHELTER IMPROVEMENT BOARD
GOVT. OF NCT OF DELHI
OFFICE OF THE EXECUTIVE ENGINEER C-6**

NAME OF WORK : Pay & Use (JSC)

SUB HEAD : Providing and re-laying blocks sewer line for JSC Code No. 47CJ0817 at JJ Basti Janta Jeevan Camp opposite Vayusenabad Tigari Part-I near Dustbin, A-Block.

S.No.	DSR Code	Item	Qty	Unit	Estimated Rate		Amount
					Figure	Words	
1	2.10	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :					
	2.10.1	All kinds of soil					
	2.10.1.1	Pipes, cables etc, not exceeding 80 mm dia. but not exceeding 300 mm dia					
						Rupees Two Hundred Twenty Five and Paise Forty Five only	
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	40.50	m	225.45		9130.73
	4.1.3	1:2:4 (1 cement : 2 coarse sand(zone-III) : 4 graded stone aggregate 20 mm nominal size)	324				
			2.25	Cum	5481.95	Rupees Five Thousand Four Hundred Eighty One and Paise Ninety Five only	12334.39
	4.1.10	1:5:10 (1 cement : 5 coarse sand(zone-III) : 10 graded stone aggregate 40 mm nominal size)	2.63				
			2.03	Cum	4209.05	Rupees Four Thousand Two Hundred Nine and Paise Five only	8544.37
3	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :					
	19.6.3	250 mm dia. R.C.C. pipe	40.50	m	482.05	Rupees Four Hundred Eighty Two and Paise Five only	19523.03

4	19.9	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom and 0.56 m dia at top in cement mortar 1:4 (1 cement : 4 coarse sand), in side cement plaster 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size), and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement, all complete as per standard design :					
	19.9.1	0.91 m deep with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560 mm internal diameter conforming to I.S. 12592, total weight of cover and frame to be not less than 182 kg., fixed in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including centering, shuttering all complete. (Excavation, foot rests and 12 mm thick cement plaster at the external surface shall be paid for separately) :					
	19.9.1.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	4.00	Each	8683.75	Rupees Eight Thousand Six Hundred Eighty Three and Paise Seventy Five only	34735.00

Total Rs. **84267.51**

Add CI @ 15.69% **13221.57**

Total Rs. **97489.08**

Less 9.50% as per orders of Delhi Govt. **-9261.46**

Total Rs. **88227.62**

Add 1% Contingencies, 1% Labour cess, 1% Quality Assurance **882.28**

92220.07
14469.32
106689.39
10135.49
96553.90
1021.42