

**DELHI URBAN SHELTER IMPROVEMENT BOARD
GOVERNMENT OF NCT OF DELHI
OFFICE OF THE EXECUTIVE ENGINEER/C-03**

2nd floor, Circle Office Bldg.,
Road No.28, Shivaji Place,
Raja Garden, New Delhi-110027

No. NIQ No.15/EEC-3/DUSIB/2020-21

Dated: 31.03.2021

NOTICE INVITING QUOTATIONS

Executive Engineer/C-03 on behalf of DUSIB invites quotations on percentage rate basis in sealed cover from intending agencies who are qualified Engineering firm and having specialisation in structural design for the work as given below:-


S.N.	Name of work	Estimated Cost (Rs)	Time Allowed for completion of work
1	NOW :- Built up Facilities (Revenue) SH :-Urgent repair of defects on need basis in BVK at X Block Mangolpuri. (PID-13204)	92,029.00	03 Days.

The firms who wish to participate in quotation shall submit their quotation along with the following documents, failing which their quotation is liable to be rejected

1. Copy of their registration certificate.2. Copy of pan card.3. Copy of Registration under GST.

The quotations should reach to the Office of the Executive Engineer,C-03,DUSIB, 2nd floor, Circle Office Bldg., Road No.28, Shivaji Place, Raja Garden, New Delhi-110027 latest by 3.00 PM on 3.04.2021 which shall be opened on the same day at 3:30PM in the presence of intending quotationers or their representatives. The intending quotationers may collect the schedule of quantities and other information from the office of the undersigned by 3:00 PM on 3.04.2021. The terms and conditions of the NIQ are as follows:-

1. The work shall be carried out as per terms and conditions of CPWD specifications with up to date correction. Conditional quotations shall be liable for rejection.
2. For any disputes the matter shall be referred to SE-I for final decision and same shall be binding upon both the parties.
3. Necessary statutory deductions will be made as per prevailing tax rates.
4. Works shall be completed as per satisfaction of Engineer-in-charge.
5. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.
6. Completed three no. Of similar nature of works of atleast 80% of cost be attached along with the quotation. This will be the deciding factor for the acceptance of the quotation.
7. Quoted Rates are inclusive of all the applicable taxes.



**EXECUTIVE ENGINEER-C-03
DUSIB**

DELHI URBAN SHELTER IMPROVEMENT BOARD

OFFICE OF THE EXECUTIVE ENGINEER C-3

NAME OF WORK :- Built up facilities

Sub - Head :- Urgent repair of defects on need bases in BVK at X block Mangolpuri

S. No.	Ref. No.	Description of work	No.or Qty.	Unit	Rate Rs.	Rate in Words	Amount (In Rs.)
1	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering . All work upto plinth level. 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	1.00	cum	5481.95	Rs Five Thousand Four Hundred EightyOne Paise NinetyFive Only	5481.95
2	4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering All work upto plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) : 10 graded stone aggregate 40 mm nominal size)	1.00	cum	4209.05	Rs Four Thousand Two Hundred Nine Paise Five Only	4209.05
3	10.1	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	50.00	Kg	58.45	Rs FiftyEight Paise FourtyFive Only	2922.50
4	12.231.1	Providing sand stone slab for roofing and laying them in cement mortar 1 : 4 (1 cement : 4 coarse sand) over wooden karries or R.C.C. battens or structural steel sections (Karries or battens or structural steel sections to be paid eparately), including pointing the ceiling joints with cement mortar 1:3 (1 cement : 3 fine sand) complete :Red sand stone slab 40 to 50 mm thick	2.00	Sqm	560.05	Rs Five Hundred Sixty Paise Five Only	1120.10
5	6.4.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:4 (1 cement : 4 coarse sand)	1.00	cum	5801.50	Rs Five Thousand Eight Hundred One Paise Fifty Only	5801.50
6	11.36	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except begundy, bottle green, black of any size as approved by Engineer - in - Charge in skirting, risers of steps and dados over 12 mm thick bed of Cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete	10.00	sqm	744.80	Rs Seven Hundred FourtyFour Paise Eighty Only	7448.00

7	11.40	Providing and laying rectified Glazed Ceramic floor tiles 300x300 mm or more (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand) including pointing the joints with white cement and matching pigments etc., complete.	5.00	Sqm	901.05	Rs Nine Hundred One Paise Five Only	4505.25
8	13.4.1	12 mm cement plaster of mix: 1:4 (1 cement : 4 coarse sand)	10.00	sqm	180.85	Rs One Hundred Eighty Paise EightyFive Only	1808.50
9	13.5.1	15mm cement plaster of mix1:4 (1 cement : 4 coarse sand)	10.00	sqm	209.65	Rs Two Hundred Nine Paise SixtyFive Only	2096.50
10	13.16.1	6 mm cement plaster to ceiling of mix : 1:3 (1 cement : 3 fine sand)	5.00	sqm	143.80	Rs One Hundred FortyThree Paise Eighty Only	719.00
11	13.18	Neat cement punning	5.00	sqm	42.60	Rs FourtyTwo Paise Sixty Only	213.00
12	15.2.1	Demolishing cement concrete manually / by mechanical means and disposal of material within 50 metres lead as per direction of Engineer - in - Charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design	14.88	cum	997.05	Rs Nine Hundred NinetySeven Paise Five Only	14836.10
13	15.2.2	Demolishing cement concrete manually / by mechanical means and disposal of material within 50 metres lead as per direction of Engineer - in - Charge.Nominal concrete 1:4:8 or leaner mix (i/c equivalent design	2.00	cum	615.15	Rs Six Hundred Fifteen Paise Fifteen Only	1230.30
14	15.7.4	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in - Charge. In cement mortar	1.00	cum	842.75	Rs Eight Hundred FortyTwo Paise SeventyFive Only	842.75
15	15.25	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	5.00	sqm	109.35	Rs One Hundred Nine Paise ThirtyFive Only	546.75
16	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	5.00	Sqm	22.40	Rs TwentyTwo Paise Fourty Only	112.00
17	15.60	Disposal of building rubbish / malba / similar unserviceable,dismantled or waste materials by mechanical means,including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts	15.00	cum	120.55	Rs One Hundred Twenty Paise FiftyFive Only	1808.25

18	17.2. 2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked black solid	1	no.	3395.45	Rs Three Thousand Three Hundred NinetyFive Paise FourtyFive Only	3395.45
19	18.7. 3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall. 25 mm nominal outer dia Pipes	10.00	metre	216.20	Rs Two Hundred Sixteen Paise Twenty Only	2162.00
20	18.7. 5	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall. 40 mm nominal outer dia Pipes	10.00	metre	385.50	Rs Three Hundred EightyFive Paise Fifty Only	3855.00
21	18.18 .3	Providing and fixing ball valve (brass) of approved quality complete High or low pressure with plastic floats :25 mm nominal bore	2	each	331.95	Rs Three Hundred ThirtyOne Paise NinetyFive Only	663.90
22	18.21 .1.1	Providing and fixing unplasticised P.V.C. connection pipe with brass unions: 30 cm length- : 15 mm nominal bore	2	each	59.40	Rs FiftyNine Paise Fourty Only	118.80
23	18.21 .2.2	Providing and fixing unplasticised P.V.C. connection pipe with brass unions : 45 cm length- : 15 mm nominal bore	2	each	67.80	Rs SixtySeven Paise Eighty Only	135.60
24	18.46 .1	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 15 mm nominal bore	4	each	147.75	Rs One Hundred FourtySeven Paise SeventyFive Only	591.00
25	18.46 .3	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 25 mm nominal bore	5	each	205.80	Rs Two Hundred Five Paise Eighty Only	1029.00

26	18.46 .5	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 40 mm nominal bore	4	each	298.75	Rs Two Hundred NinetyEight Paise SeventyFive Only	1195.00
27	18.48 .A	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.Circular tank	2000	per litre	7.25	Rs Seven Paise TwentyFive Only	14500.00
28	18.54 .3	Providing and fixing PTMT bib cock of approved quality and colour. 15 mm nominal bore, 165 mm long. Weighing not less than 110 gms.	5	each	157.90	Rs One Hundred FiftySeven Paise Ninety Only	789.50
29	18.55 .1	Providing and fixing PTMT stop cock of approved quality and colour. 15 mm nominal bore, 86 mm long. Weighing not less than 88 gms.	4	each	103.30	Rs One Hundred Three Paise Thirty Only	413.20
30	19.19 .3.1	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality Circular shape 560 mm internal diameter. HD - 20	1.00	no.	1300.95	Rs One Thousand Three Hundred Paise NinetyFive Only	1300.95
	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS :5382 leaving 10 mm gap for thermal expansion.					
31	12.42 .5.2	Bend 87.5°. 110 mm bend	2.00	no.	113.10	Rs One Hundred Thirteen Paise Ten Only	226.20
32	12.42 .6.2	Shoe (Plain) 110 mm Shoe	2.00	no.	98.00	Rs NinetyEight Only	196.00
33	19.21 .2	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand) finished with affloating coat of neat cement and making necessary channels for the drains etc. complete : For pipes 250 to 300 mm diameter	1.00	each	463.45	Rs Four Hundred SixtyThree Paise FortyFive Only	463.45
34	9.63.1	Providing and fixing ISI marked oxidised M.S. tower bolt black finish,(Barrel type) with necessary screws etc. complete :250x10 mm For Doors	2.00	each	64.00	Rs SixtyFour Only	128.00

35	9.63.3	Providing and fixing ISI marked oxidised M.S. tower bolt black finish,(Barrel type) with necessary screws etc. complete 150x10 mm for Window	2.00	each	44.10	Rs FourtyFour Paise Ten Only	88.20
36	9.66.1	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete :125	4.00	each	28.60	Rs TwentyEight Paise Sixty Only	114.40
37	9.56.2	Providing and fixing ISI marked, IS : 1341, M.S. heavy weight butt hinges with necessary screws etc. complete, 100x75x3.50 mm	2.00	each	34.95	Rs ThirtyFour Paise NinetyFive Only	69.90
38	9.56.3	Providing and fixing ISI marked, IS : 1341, M.S. heavy weight butt hinges with necessary screws etc. complete 75x60x3.10 mm	2.00	each	25.45	Rs TwentyFive Paise FourtyFive Only	50.90
39	9.62.2	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete:250x16 mm	5.00	each	142.05	Rs One Hundred FourtyTwo Paise Five Only	710.25
Total							87898.20
Add 15.69% Cost Index							13791.23
Total							101689.43
Less 9.50% Cost Index							-9660.50
Total							92028.93

EE C-3

AE-IV

EI