

DELHI URBAN SHELTER IMPROVEMENT BOARD
GOVT. OF NCT OF DELHI
OFFICE OF THE EXECUTIVE ENGINEER C-07
Office Building, Rana Pratap Bagh, Delhi-110007.

NIQ No. 01/EEC-07/DUSIB/2021-22/D- 44

Dated: 30/4/2021


NOTICE INVITING QUOTATIONS

Executive Engineer, C-07 DUSIB on behalf of Delhi Urban Shelter Improvement Board invites quotations approved and eligible contractors of CPWD, Railways, MES and Civil Wing of BSNL, M.C.D, DDA, NDMC, Delhi Jal Board, I&F Deptt., Delhi in appropriate class on % rate basis as per schedule of quantities attached in sealed cover for the following works:-


S. No.	Name of work	Estimated Cost	Time of completion
1	Pay and Use JSC. Sub-head: Provision of water facilities and allied civil work in 60 Nos. Toilet Cubical (2 Blocks of 30 seater each) at COVID Centre, Sant Nirankari Ground, Burari (PID No.13468).	Rs.2,44,254.00	07 days after the date of issue of work order.

The quotations along with copy of valid Registration, PAN and GST should reach to the office of the Executive Engineer, C-07, DUSIB Office Building, Rana Pratap Bagh, Delhi-110007 latest by 12.30 PM on 30-04-2021 which shall be opened on the same day at 12.40 PM in the presence of intending quotationers or their representatives. The intending quotationer may collect the schedule of quantities and other information from the office of the Executive Engineer, C-07, DUSIB. The terms & Conditions of the NIQ are as follows:-

1. The work shall be carried out as per CPWD specifications 2019 Vol-I & II with upto date correction slips.
2. Cement/steel required shall be arranged by the Agency and same shall conform to relevant specification/I.S. Code.
3. Payment shall be made as per actual measurement at site of work.
4. No T& P shall be issued.
5. No extra charges shall be paid except for the rates quoted.
6. Conditional quotations shall be liable to rejection.
7. For any disputes the matter shall be referred to CE-II, DUSIB for final decision and the same shall be binding upon both the parties.
8. Necessary statutory deductions will be made as per prevailing Law.
9. Work shall be completed to the satisfaction of Engineer-in-charge.
10. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.


EXECUTIVE ENGINEER, C-07
D.U.S.I.B. (GNCTD)

NOTICE BOARD


30/4/21

Name of Work : - Pay and Use JSC

Sub-Head :-Provision of water facilities and allied works in 60 Nos. Toilet Cubicals (2 Blocks of 30 seats each) at COVID Centre Sant Nirankari Ground, Burari. (PID No. 13468)

SCHEDULE OF WORK						
S. No.	DISCRIPTION OF WORK	Qty	UNIT	RATE		AMOUNT (Rs.)
				In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	1.22	cum	166.40	RUPEES ONE HUNDRED SIXTY SIX PAISE FOURTY ONLY	203.01
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size).	2.00	cum	3959.70	RUPEES THREE THOUSAD NINE HUNDRED FIFTY NINE PAISE SEVENTY ONLY	7919.40
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	2.00	cum	5481.95	RUPEES FIVE THOUSAND FOUR HUNDRED EIGHTY ONE PAISE NINETY FIVE ONLY	10963.90
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	2.00	cum	4751.65	RUPEES FOUR THOUSAND SEVEN HUNDRED FIFTY ONE PAISE SIXTY FIVE ONLY	9503.30

5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :Cement mortar 1:4 (1 cement : 4 coarse sand)	5.00	sqm	593.50	RUPEES FIVE HUNDRED NINETY THREE PAISE FIFTY ONLY	2967.50
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	800.00	kg	85.95	RUPEES EIGHTY FIVE PAISE NINETY FIVE ONLY	68760.00
7	Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with sand, with common burnt clay non modular bricks.	72.00	sqm	516.00	RUPEES FIVE HUNDRED SIXTEEN PAISE NIL ONLY	37152.00
8	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	10.00	sqm	160.35	RUPEES ONE HUNDRED SIXTY PAISE THIRTY FIVE ONLY	1603.50
9	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)	10.00	sqm	185.20	RUPEES ONE HUNDRED EIGHTY FIVE PAISE TWENTY ONLY	1852.00
10	Neat cement punning.	20.00	sqm	42.60	RUPEES FOURTY TWO PAISE SIXTY ONLY	852.00
11	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	50.00	sqm	78.40	RUPEES SEVENTY EIGHT PAISE FOURTY ONLY	3920.00

12	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External Work 40 mm nominal outer dia pipes.	5.00	metre	321.15	RUPEES THREE HUNDRED TWENTY ONE PAISE FIFTEEN ONLY	1605.75
13	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External Work 32 mm nominal outer dia pipes.	20.00	metre	250.55	RUPEES TWO HUNDRED FIFTY PAISE FIFTY FIVE ONLY	5011.00
14	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External Work 25 mm nominal outer dia pipes.	150.00	metre	191.65	RUPEES ONE HUNDRED NINTY ONE PAISE SIXTY FIVE ONLY	28747.50

15	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External Work 20 mm nominal outer dia pipes.	125.00	metre	149.30	RUPEES ONE HUNDRED FORTY NINE PAISE THIRTY ONLY	18662.50
16	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 40 mm nominal bore	2.00	each	298.75	RUPEES TWO HUNDRED NINTY EIGHT PAISE SEVENTY FIVE ONLY	597.50
17	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 32 mm nominal bore	4.00	each	240.65	RUPEES TWO HUNDRED FOURTY PAISE SIXTY FIVE ONLY	962.60
18	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 25 mm nominal bore	8.00	each	205.80	RUPEES TWO HUNDRED FIVE PAISE EIGHTY ONLY	1646.40
19	Providing and fixing PTMT push cock of approved quality and colour. 15mm nominal bore, 98 mm long, weighing not less than 75 gms	40.00	each	91.70	RUPEES NINTY ONE PAISE SEVENTY ONLY	3668.00

