

NIQ No. 07/EE/C-2/DUSIB/2021-22/D- 266

Dated: 15.09.2021

## NOTICE INVITING QUOTATION

Executive Engineer, C-1 DUSIB on behalf of Delhi Urban Shelter Improvement Board invites quotations from intending agencies who are registered either with DDA, MCD, CPWD, BSNL(Civil Wing), I&F,MES, Railway, Delhi State eligible services provider registered on Registered of company / firms who are essentially registered on Delhi Govt. e-tendering portal etc. in appropriate class, on percentage rate basis in sealed cover for the following works:-

SL. NO	Name of work	Estimated Cost	Time of Completion
1.	<b>Name of Work:</b> - C/o 7620 (G+4) five storeyed low cost houses for slum dwellers (Under JNNURM) at Savda Ghewra Ph-III <b>S.H.-</b> Construction of Damaged/abundant boundary wall of the housing complex of group-II for 3560 Flats on the back side (between I block and Flood Drain) at Savda Ghewra Ph-III.	Rs.975569.00	30 days

The firms who wish to participate in quotation shall submit their quotation along with the following documents, failing which their quotation is liable to be rejected.

1. Copy of their registration certificate.
2. Copy of pan card.
3. Copy of Registration under GST.


The quotations should reach to the office of the Executive Engineer,C-2, DUSIB, Raja Garden, New Delhi-110027 latest by 3.00 PM on 16/09/2021 which shall be opened on 16/09/2021....at.3.30 PM in the presence of intending quotationers or their representatives.

The intending quotationers may collect the schedule of quantities and other information from the office of the Executive Engineer,C-2, DUSIB. The terms & Conditions of the quotation are as follows:-

1. The work shall be carried out as per CPWD specifications.
2. Payment shall be made as per actual measurement at site of work.
3. Water and electricity is to be arranged by agency.
4. conditional quotation shall be liable to rejection.
5. Statutory recoveries shall be deducted from the bills of contractor as per rules.
6. For any disputes the matter shall be referred to SE-I DUSIB for final decision and the same shall be binding upon both the parties
7. Work shall be completed to the satisfaction of Engineer-in-charge.
8. Debarred/blacklisted agencies shall not be permitted to submit quotations.
9. The Structural design of UGR shall cover the scope of entire work order the scheme as per enclosed drawing.
10. Security @10% shall be recovered from the gross amount of the each bill.
11. The panel action for withdrawing the bid by the quotationer shall be viewed seriously and the competent authority reserved the right to debar for not participating in the tender in DUSIB for five years.

NOTICE BOARD

DUSIB website

  
15/09/2021  
EXECUTIVE ENGINEER,C-2

## Office of the Executive Engineer C-2, DUSIB

Name of Work:- C/o 7620 (G+4) five storeyed low cost houses for slum dwellers (under JNNURM) at Savda Ghewra Ph-III

Sub Head: Construction of Damaged/abundant boundary wall of the housing complex of group-II for 3560 Flats on the balck side (between I block and Flood Drain) at Savda Ghewra Ph-III

S. no.	DSR REF	Description of Item	Qty	Unit	Rate	Rate in words	Amount
1	15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.. In cement mortar	70.75	Cum	842.75	Rupees Eight Hundred Forty Two and Seventy Five Paise Only	59624.56
2	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. :All kinds of soil.	30.55	Cum	166.40	Rupees One Hundred Sixty Six and Forty Paise Only	5083.52
3	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	<del>70.75</del> 35.38	Cum	120.55	Rupees One Hundred Twenty and Fifty Five Paise Only	<del>8528.91</del> 4265.00
4	4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand(zone-III) : 10 graded stone aggregate 40 mm nominal size)	6.75	Cum	4209.05	Rupees Four Thousand Two Hundred Nine and Five Paise Only	28411.09



5	6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	34.46	Cum	4751.65	Rupees Four Thousand seven Hundred fifty one and sixty five Paise Only	163741.86
6	6.32.2	Brick work with clay flyash F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	22.51	Cum	5739.95	Rupees Five Thousand seven Hundred thirty nine and ninety five Paise Only	129206.27
7	4.10	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (Zone III) : 4 graded stone aggregate 12.5mm nominal size).	22.51	Sqm	263.10	Rupees Two Hundred Sixty Three and Ten Paise Only	5922.36
8	4.13	Providing and applying a coat of residual petroleum bitumen of grade of VG-10 of approved quality using 1.7kg per square metre on damp proof course after cleaning the surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil.	33.77	Sqm	91.90	Rupees Ninety One and Ninety Paise Only	3103.46
9	10.2 5.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. : In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	362.20	Kg	85.95	Rupees Eighty Five and Ninety Five Paise Only	31131.09
10	5.9.1 6.1	Centering and shuttering including strutting, propping etc. and removal of form for :walls ( any thickness) including attached plaster buttresses,plinth and string course etc	108.25	Sqm	378.60	Rupees three Hundred seventy eight and sixty Paise Only	40983.45

11	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand(zone-III) : 4 graded stone aggregate 20 mm nominal size)	0.50	Cum	5481.95	Rupees Five Thousand Four Hundred Eighty One and Ninety Five Paise Only	2740.98
12	16.5 3	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length ( total length 90 m) having 50 no rounds per 6 metre length, upto 3m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) /Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	97.88	Metr	255.00	Rupees Two Hundred Fifty Five Only	24959.40
13	13.6 1.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	73.26	Sqm	78.40	Rupees Seventy Eight and Forty Paise Only	5743.58

14	4.2.3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., up to floor five level, excluding the cost of centering, shuttering and finishing : Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., up to floor five level, excluding the cost of centering, shuttering and finishing :	2.33	Cum	6547.70	Rupees Six Thousand Five Hundred Fourty seven and Seventy Paise Only	15256.14
15	15.8.3	Removing mortar from bricks and cleaing bricks including stacking within a lead of 50 m (stacks of cleaned bricks shall be measured): From brick work in cement mortar	17690.00	100 0 Nos.	2798.60	Rupees Two Thousand Seven Hundred Ninety Eight and Sixty Paise Only	49507.23



16	app. Item	24 mm thick washed marble chips plaster exterior walls height up to 10 meter above ground level in two layers under layer 12mm cement plaster 1:4 (1 cement : 4 coarse sand) furrowing the under layer with scracling tool, applying cement slurry on the under layer @ 2 kg of cement per sqm and top layer 12 mm thick with marblePlaster 4:7 ( Cement :7 Marble chips as per 4mm size) in panels with groove all round as per approved patteran i/c sarubbing and washing the top layer with brushes and water to expose the stone chipping complete as per specification and direction of engineer- in charge ( Payment for providing groove shall be made sepratly)	412.28	sqm	487.90	Rupees Four Hundred Eighty Seven and Ninety Paise Only	201151.41
17	13.7 6	Forming groove of uniform size from 12x12mm and upto 25x15mm in the top layer of washed stone grit plastered surface as per approved pattern, including providing and fixing aluminum channels of appropriate size and thickness (not less than 2 mm), nailed to the under layer with rust proof screws and nails and finishing the groove complete as per specifications and direction of the Engineer-in-Charge.	1236.84	m	71.60	Rupees Seventy One and Sixty Paise Only	88557.74
18	13.7 1	Lettering with black Japan paint of approved brand and manufacture	32.50	per letter per cm ht.	2.70	Rupees Two and Seventy Paise Only	87.75
19	5.22 A.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500 D or more.	782.65	Kg	56.60	Rupees Fifty Six and Sixty Paise Only	44297.99

20	5.1.2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	2.52	Cum	6215.35	Rupees Six Thousand Two Hundred Fifteen and Thirty Five Paise Only	15662.68
21	5.2.2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)	4.19	Cum	7145.80	Rupees Seven Thousand One Hundred Forty Five and Eighty Paise Only	29940.90
22	Basic Rate DSR	Recovery for servisable brick	17690.00	No	4.00		-70760.00
		A					-882882.39
		Add 22.69% for prevailing cost of index issued by CPWD on DSR 2016 on A					200326.01
		B					1083208.40
		Less 9.5 % for cost index on DSR 2014 as per GNCTD orders on B					-102904.80
		Total					980303.60

878618.56  
199358.55  
1077977.09  
102407.82  
975569.26