

DELHI URBAN SHELTER IMPROVEMENT BOARD
OFFICE OF THE EXECUTIVE ENGINEER, C-10
INDERLOK DELHI-110035.

No. NIQ No.03/EEC-10/DUSIB/2021-22/D- 506

Dated: 25/10/2021


NOTICE INVITING SPOT QUOTATIONS

Executive Engineer, C-10, DUSIB on behalf of Delhi Urban Shelter Improvement Board invites quotations from intending agencies who are registered with CPWD, Railways, MES, Civil Wing of BSNL, M.C.D, DDA, NDMC, Delhi Jal Board, Irrigation & Flood Deptt, Delhi, Delhi State PWD etc. in appropriate class on percentage rate basis in sealed cover for the following works:-

S.N	Name of work	Estimated Cost	Time of Completion
1	N.O.W: Construction of Night Shelter Sub Head - Carrying out Emergent work to provide water supply to FRRO Centre at Night Shelter Building, Shahzada Bagh in AC-19, Sadar Bazar.	92,099/-	15 days

The quotations along with copies of PAN Card, Aadhar Card of the proprietor of firm, GST registration and valid registration certificate of the department registered with should be submitted in the office of the Executive Engineer, C-10, DUSIB, Inder Lok, Delhi-110035 latest by 2.00 PM on 28.10.2021 which shall be opened on the same day at 3.00 PM in the presence of intending quotationers or their representatives. The intending quotationer may collect the schedule of quantities and other information from the office of the Executive Engineer, C-10, DUSIB. The terms & Conditions of the NIQ are as follows:-


1. The work shall be carried out as per directions of the Engineer-in-charge.
2. Payment shall be made only after successful completion of the function to the entire satisfaction of the Competent Authority / Engineer-in-charge.
3. No T&P shall be issued by the Department.
4. No extra charges shall be paid except for the rates quoted.
5. Conditional quotations shall be liable to rejection summarily.
6. Necessary statutory deductions will be made as per prevailing Law.
7. Debarred/blacklisted agencies shall not be permitted to participate in the NIQ process.
8. NIQ will be issued to the intended participants only after verification of documents related to NIQ.
9. The participants should submit Demand Draft of Rs.10000/- as security deposit in favour of Executive Engineer, C-10, DUSIB along with other requisite document before issue of NIQ.


25.10.2021
EXECUTIVE ENGINEER, C-10
D.U.S.I.B. (GNCTD)

NOTICE BOARD

Copy to:

- 4) SE, Circle IV (DUSIB) for kind information please.
- 5) ACA IV for kind information
- 6) All AEs/C 10 4 AAO/C-10 5 HC/C 10 6 Office copy.


25.10.2021
EXECUTIVE ENGINEER, C-10
D.U.S.I.B. (GNCTD)

Abstract of Cost-Original Estimate

C-10

Sub-Division

Branch
Name of Work :

Construction of Night Shelter.
Sub Head:- Carrying out emergent work to provide water supply to FRRO Centre at Night Shelter Building, Shahzada Bagh in AC-19 Sadar Bazar.

ITEM No	CODE	SUB-HEADS AND ITEM OF WORK	QUANTITY	RATE (Rs)	UNIT	AMOUNT (Rs)
1	18.19	Providing and fixing gun metal non- return valve of approved quality (screwed end) :				
1.1	18.19.2	32 mm nominal bore				
1.1.1	18.19.2.1	Horizontal	2	552.45	each	1,104.90 SR
2	18.54	Providing and fixing PTMT bib cock of approved quality and colour.				
2.1	18.54.2	15 mm nominal bore, 122mm long, weighing not less than 99 gms	10	143.95	each	1,439.50 SR
3	18.46	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :				
3.1	18.46.4	32 mm nominal bore	4	240.65	each	962.60 SR
4	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. EXTERNAL WORK				
4.1	18.9.4	32 mm nominal outer dia Pipes	215	250.55	metre	53,868.25 SR
5	18.17	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :				
5.1	18.17.2	32 mm nominal bore.	2	500.75	each	1,001.50 SR
6	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
6.1	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	4.3	5,481.95	cum	23,572.38 SR
7	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
7.1	15.2.1	Nominal concrete 1:3:6 or richer mix (i.e equivalent design mix)	1	997.05	cum	997.05 SR
		Total				82,946.18 ✓
		Add PWD Cost Index @22.69% (On SR&DR Total 82,946.18)				18,820.49 ✓
		Total				1,01,766.6 ✓
		Deduct Cost Index @9.5% (On SR&DR Total 82,946.18+18,820.49)				(-) 9,667.83 ✓
		Total				92,098.84 ✓
		Add Contingencies @1%				920.99 ✓
		Grand Total				93,019.83 ✓
		Say				93,019.83 ✓

Detail estimate tech checked by R 93,020/-